

Executive Order VR-205-B
VST Phase II EVR System with Hirt Thermal Oxidizer

Exhibit 3
Performance Standards and Specifications

Part I - VST Manufacturing Performance Standards and Specifications

The VST Phase II EVR System and all components shall be manufactured in compliance with the performance standards and specifications in CP-201 (amended May 25, 2006), as well as the requirements specified in this Executive Order. All components (Exhibit 1) shall be manufactured as certified; no change to the equipment, parts, design, materials or manufacturing process shall be made unless approved in writing by the Executive Officer or Executive Officer delegate. Unless specified in Exhibit 2 or in the **ARB Approved Installation, Operation and Maintenance Manual**, the requirements of this section apply to the manufacturing process and are not appropriate for determining the compliance status of a gasoline dispensing facility.

1. NOZZLES

Every nozzle shall be tested at the factory. Every nozzle shall have affixed to it a card or label stating the performance specifications listed below, and a statement that the nozzle was tested to, and met, the following specifications.

- a. The nozzle vapor valve leak rate shall not exceed 0.07 cubic feet per hour (CFH) at a pressure of +2 inches water column (WC) when tested in accordance with the latest version of TP-201.2B.
- b. The nozzle automatic shut off feature is tested at all service clip settings as well as handheld in accordance with Underwriters Laboratories (UL) Standard 842.
- c. The nozzle's primary and secondary shut-off mechanism shall be identical to the design that passed the California Department of Food and Agriculture Division of Measurement Standards Article 2 (DMS 6-6-97).
- d. The nozzle is manufactured to the specifications that passed all tests conducted during the ARB certification for the following:

TP-201.2C	- Spillage from Phase II Systems
TP-201.2D	- Post Fueling Drips from Nozzles
TP-201.2E	- Gasoline Liquid Retention and Spitting in Nozzles and Hoses
TP-201.2J	- Nozzle Pressure Drop
- e. The nozzle vapor collection boot is manufactured such that the force necessary to compress the nozzle bellows 0.5 inches is in the range of 10-16 pounds force.
- f. The terminal end of each nozzle shall be manufactured in accordance with the specifications referenced in Section 4.7.3 of CP-201.

2. COAXIAL HOSES

- a. Every coaxial hose is tested for continuity and pressure tests in accordance with UL Standard 330.
- b. Every coaxial hose is manufactured to the standards and specifications that passed all tests conducted during the ARB certification for the following:
 - Exhibit 5 - Liquid Removal Test Procedure (for curb hoses)
 - TP-201.2J - Hose Pressure Drop (for curb and whip hoses)

3. BREAKAWAY COUPLINGS

- a. Every breakaway coupling is tested for continuity and pressure tests in accordance with UL Standard 567.
- b. Every breakaway coupling is manufactured to the standard that passed all tests conducted during the ARB certification for the following:
 - TP-201.2J - Breakaway Pressure Drop

Part II - Hirt Manufacturing Performance Standards and Specifications

The Hirt VCS 100 thermal oxidizer and all components shall be manufactured in compliance with the performance standards and specifications in CP-201 (amended May 25, 2006), as well as the requirements specified in this Executive Order. All components (Exhibit 1) shall be manufactured as certified; no change to the equipment, parts, design, materials or manufacturing process shall be made unless approved in writing by the Executive Officer or Executive Officer delegate. Unless specified in Exhibit 2 or in the ***ARB Approved Installation, Operation and Maintenance Manual***, the requirements of this section apply to the manufacturing process and are not appropriate for determining the compliance status of a gasoline dispensing facility.

1. HIRT VCS 100 THERMAL OXIDIZER

- a. The VCS 100 processor is subjected to an assembly quality check.
- b. The VCS 100 processor is visually inspected to verify identification, caution/warning, electrical, and other Agency labels are in place.
- c. The VCS 100 processor is subjected to vacuum and pressure leak tests.
- d. The VCS 100 processor is subjected to the following functional tests:
 - i. Power test;
 - ii. Verify set point of vacuum sensor switch;
 - iii. Verify operation of main vapor valve;
 - iv. Verify flow rate of pilot and main vapor valves; and
 - v. Dielectric test.